Calabash Creek

Federal Channel

Depth Ft MLLW

- Greater than 12
- 10 - 12
- 8 - 10
- 6 - 8
- Less than 6

USDA, FSA, APFO

0 500 1,000 2,000 Feet

1 inch = 500 feet

N W E S

Survey Area:	**Calabash Creek**
Survey Date:	10-29-2013
Survey Crew:	USACE Survey Team
Survey File Name:	20131029_ICR_CB_CS
Imagery/Background:	2011 NAIP
Mapped By:	

US Army Corps Of Engineers®
Charleston District

Notes:
- Soundings are expressed in positive feet and tenths and are referenced the Mean Lower Low Water (MLLW) datum.
- Project surveyed with USACE survey vessels equipped with GPS positioning and hydrographic survey equipment that meets USACE Navigation and Dredging standards for soft bottom hydrographic surveys.
- Soundings are calibrated to tide gauges that are set to MLLW and referenced to published benchmarks.
- Horizontal Datum: State Plane NAD-83 SC-3900 Intl Feet
- Project was designed by the Charleston District of the U.S. Army Corp of Engineers. The initials or signatures and registration designations of individuals appear on these project documents within the scope of their employment by ER 1110-1-8152.
- Maps and associated information represents the result of surveys made on the date indicated and can only be considered as indicating the general condition existing at that time. These conditions are subject to rapid change due to shoaling events. A prudent mariner should not rely exclusively on the information provided here.
- Aids to Navigation obtained from the U.S. Coast Guard Light List.