NOTES:
1. SOUNDINGS ARE IN FEET AND REFERENCED TO MEAN LOW WATER.
2. DATE OF CONDITION SURVEY: DECEMBER 9, 2004.
3. VERTICAL DATUM FOR TOPOGRAPHY IS NAVD88.

COORDINATES					
PT.	STATION	NAD 27		NAD 83	
NO.	W/OFFSET	EAST (X)	NORTHING (Y)	EAST (X)	NORTHING (Y)
	1120+30.93N 200L	2,518,364.86	491,116.74	2,518,366.12	491,283.27
	1120+30.93N 200R	2,518,443.76	490,720.54	2,518,445.12	490,887.12
	1118+38.71N 200R	2,518,315.62	490,675.28	2,518,317.01	490,841.83
	1118+38.71N 200L	2,518,130.58	491,034.12	2,518,131.88	491,200.59
	1107+42.34N 300R	2,517,576.98	490,033.32	2,517,578.60	490,199.71
	1107+42.34N 200R	2,517,493.48	490,096.80	2,517,495.09	490,263.17
	1091+78.22N 200L	2,516,624.81	488,850.20	2,516,626.83	489,016.42
	1091+78.22N 200R	2,516,978.45	488,651.01	2,516,980.50	488,817.35
	1091+78.22N 160R	2,516,943.09	488,670.93	2,516,945.14	488,837.26
	1076+64.37N 200R	2,516,041.86	487,501.26	2,516,044.31	487,667.43
	1076+64.37N 200L	2,515,647.95	487,650.97	2,515,650.38	487,817.01
	1076+64.37N 160L	2,515,687.34	487,636.00	2,515,689.77	487,802.06

U.S. Army Corps of Engineers
Charleston District
69A Hagood Ave
Charleston, SC 29403-5107

LEGEND

BUILDING
FENCE
GUARD RAIL
TREE LINE
INDIVIDUAL TREE
POWER POLE
LIGHT POLE
WATER
WALL
RETAINING WALL
SHRUB
BRUSH-MARSH LINE
POST
PAVED ROAD
UNPAVED ROAD
NAVAID GREEN G-46
NAVAID RED R-45
DISPOSAL AREA
GPS CONTROL POINT
H&V CONTROL
U S HIGHWAY
STATE HIGHWAY
ROAD NUMBER 30
WATERWAY
ANCHORAGE A
WRECK W
MONUMENT M

WINYAH BAY TO CHARLESTON

SHEET INDEX

WC-1, WC-2, WC-3, WC-4, WC-5, WC-6, WC-7, WC-8, WC-9a, WC-10a, WC-11, WC-12, WC-13, WC-14, WC-15, WC-16, WC-17, WC-18

SPECIAL NOTE: THE INFORMATION SHOWN ON THIS DRAWING REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES INDICATED ON EACH MAP AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITIONS EXISTING ON THAT DATE.

NOTE:

ALL COORDINATES SHOWN ARE IN THE NAD 83 SOUTH CAROLINA STATE PLANE COORDINATE SYSTEM AND VERTICAL DATUM IS NAVD 88. OFFSET MONUMENTATION IS GOVERNMENT FURNISHED FOR INFORMATION ONLY.

PREPARED BY:

NOVA Digital Systems, INC.
PHOTOGRAMMETRIC ENGINEERING,SURVEYING & GIS SERVICES
800 TOWNE CENTRE BLVD.,SUITE 400 PINEVILLE, NC 28134
FAX (704) 889-5808

FROM AERIAL PHOTOGRAPHY
FLOWN APRIL 19 - 2001
AT A SCALE 1" = 1000'

ATLANTIC INTRACOASTAL WATERWAY

CONDITION SURVEY

STA. 1069+06N TO STA. 1126+11N

WINYAH BAY TO CHARLESTON SOUTH CAROLINA

SIZE E | DRAWING NO. 9023

9023wc10a.dgn

SCALE: 1"= 200' | SHEET 10 OF 72