



**US Army Corps
of Engineers**
Charleston District

Project Fact Sheet

Murrells Inlet, SC

Georgetown County, SC

P2#: 111488

Congressional Districts: Tom Rice (SC-7)

Appropriation:

Operation & Maintenance

Phase:

NA

Business Line:

Navigation

Authority: P.L. 89-298

Location Description: The project is located on the coast of South Carolina, in Georgetown County, about 13 miles southwest of the City of Myrtle Beach, SC.

Project Description: The projects consists of maintenance of 0.6 miles of entrance channel, 3 miles of inner channel, one turning basin, one deposition basin, and two stone jetties. Prior to the 2017 effort, the channel was previously dredged in 2002.

Current Status: As of 15 April 19 - We have had several reports about beach erosion caused by the Murrells Inlet north jetty at high tide. Several team members inspected the area and determined there does not appear to be beach erosion caused by the North Jetty being underwater at high tide. The Murrells Inlet north jetty has a low weir function that is designed to be overtopped at high tide. Further evaluation is needed of the low weir jetty elevation and beach erosion, which will be done when receive the aerial lidar data in May.

FY20 Capability: President's Budget Amt: \$0

Sponsor: Georgetown County

Project Manager (PM):

Jeremy Johnson

PM Phone:

(843) 329-8132

PM Email:

Jeremy.J.Johnson@usace.army.mil